SUBJECT:

RADIO CORPORATION OF AMERICA

RCA VICTOR DIVISION

TUBE DEPT. STANDARDIZING K-2c4-Kcs HARRISON, N. J. LANCASTER, PA.

CONTACT-COATING CONTINUITY CHECK PROCEDURE

DATE Oct. 2, 1952 PAGE

STANDARDIZING NOTICE

34-17-66

SUPERSEDED DATE May 16, 1947


SCHEDULE NO. 1

PROCEDURE

MAY

1955

Resistance between coating in tube neck and external P2 contact not to exceed 2250 ohms. Check to be made after bakeout of coating, and after speed nut insertion on types concerned, using circuit shown below.



The milliammeter should read one milliampere at full deflection. Any bulb giving a reading of 0.4 milliampere or higher when the clip is attached to the P2 Contact and the spring wire is in contact with the bulb coating in the neck, is satisfactory. Any reading lower than 0.4 indicates poor contact or open circuit.

INSPECTION

Bulb preparation to check continuity between coating and anode contact button on 100% of bulb assemblies.

** Schedule No. 2 Deleted.

STANDARDIZING SECTION ENGINEERING DEPT.

SCALE-

DIMENSIONS IN

UNLESS OTHERWISE SHOWN.

DIMENSIONS SHOWN WITHOUT TOLERANCES ARE DESIGN CENTERS

1-529-16-61

PCL18749-126JK



RADIO CORPORATION OF AMERICA RCA VICTOR DIV., TUBE DEPT. 2t - X11 STANDARDIZING, LANCASTER, PA. CONTACT TOATING CONTINUITY CHECK PROCEDURE Process Specification

DATE Aug. 27, 1954 PAGE 3

STANDARDIZING NOTICE

34-17-66

SUPERSEDES


SCHEDULE NO. 3 (Initially for C73685 Tube Type)

MAY

1955

1. PROCEDURE

1. Check to be made using circuit shown below.



2. The milliammeter should read one milliampere at full deflection.

Any bulb giving a reading of 0.4 milliampere or higher is satisfactory.

Any reading lower than 0.4 indicates poor contact or open circuit.

SCALE—
DIMENSIONS IN

End of Schedule No. 3

UNLESS OTHERWISE SHOWN. DIMENSIONS SHOWN WITHOUT TOLERANCES ARE DESIGN CENTERS

* CHANGE
** ADDITION
*** DELETION

14-548-12-66 PCI25191-126110EB